

Initial Test Results of a Megawatt-Class Supercritical CO₂ Heat Engine

Timothy J. Held



ECHOGEN
power systems

Exhaust & waste heat recovery



- Covers broad range of potential application (size, temperature, “special circumstances”)
 - Gas turbine exhaust – 450-600°C, accessible thermal energy from 100-200% of GT output
 - Recip engines – 250-450°C, ~ 40-70% of engine output
 - Steel, cement, glass, other industrials > 300°C, size widely variable, often contain condensable / corrosive materials
- sCO₂ cycles offer several key advantages
 - Power output comparable to steam systems at lower cost, smaller footprint
 - Direct in-stack heat transfer (no thermal loop), single-phase
 - Fluid is low-cost, widely available, low toxicity, thermally stable and generally non-corrosive below ~ 550°C

EPS100 - description



- Waste heat recovery system
- Targeted to ~ 20-25MW gas turbine exhaust or equivalent (500-600°C, 60-75kg/s)
- Sized for $T_4 \sim 450^\circ\text{C}$, 100kg/s total CO_2 flow rate
- Process skid = heat exchangers, controls, turbopump
- Power skid = Power turbine, gearbox & generator
- CO_2 service systems = Storage tank, transfer pump and auxiliaries


The EPS100



- Designed for GE LM2500 exhaust
 - 8 MW gross, 7.3 MW net
- Physical Configuration
 - Process Skid (right)
 - Power Skid (above)
 - MCC
 - CO2 storage tank and transfer system
 - Cooling system, air or water





Cycle architectures - Simple recuperated




Low pressure ratio cycle => recuperation => can limit ΔT of heat addition

Cycle architectures – Recompression



*Recompression cycle designed for low ΔT
Not a good solution for WHR*

Cycle architectures - WHR




Multiple stages of heat transfer and expansion used to maximize power output for a given heat source $mc_p\Delta T$

Test configuration at Dresser-Rand



- Facility steam used as heat source
- Turbine inlet temperature is limited to $\sim 270^{\circ}\text{C}$
- Configuration is split recuperated – both turbines at \sim same inlet temperature



EPS100 Test Program



- Multi-phase test program (✓=complete):
 - ✓ Phase 1: Process Skid
 - ✓ Validation of components and controls
 - ✓ Phase 2: Power Skid
 - ✓ Full speed no load testing of powertrain
 - ✓ Demonstration of ability to synchronize to the grid
 - ✓ Phase 3: Process Skid Durability
 - ✓ Validate operation at operating extremes
 - Phase 4: Endurance Testing at Part-Load
 - Run to facility limits
 - Ongoing


EPS100 testing at Dresser-Rand



Key accomplishments

- Completed Phases I-III of testing
- System control and stability fully demonstrated
- Component performances meet or exceed expectations
- Turbopump run to max conditions
- Generator speed control stability demonstrated
- Power turbine electrical output = 2.35MWe max to date
- 218 hours turbopump run time
- 68 hours power turbine run time

PT power and speed summary



- Running in “island mode” due to load banks
- Speed and load ramp rates improving as controls refined


PT max power run



Turbomachinery Validation



- Power turbine and turbopump efficiencies demonstrate excellent agreement with reference curve derived by NASA.
- Turbopump test data represent operation near full power
- Power turbine data represent significantly off-design conditions of the test cycle configuration. At full power conditions efficiency is expected to be similar to turbopump




Turbine performance vs NASA TP-1730 curve. Note that TP-1730 curve ends at approximately $U_t/C_0=0.9$.

Turbopump Validation




- Measured pump efficiency is somewhat higher than predicted value.



Measured pump efficiency vs flow coefficient. Note that this is a "cloud plot" of the density of approximately 25,000 data points - the gray scale indicates the density of data points that fall within a given x,y coordinate set.


Turbopump work balance



- Difference between pump and turbine work equals expected bearing and heat losses


Heat Exchanger Validation

- Discretized heat exchanger model
 - Geometric details inferred from design point performance
 - Scaling to other conditions based on detailed heat transfer model
- Good agreement between model and data over a broad range of operating conditions.



Cloud plot of recuperator (RC-2) performance, actual vs predicted.


Test configuration



Heat and Mass Balance Cycle Model



- Detailed cycle model
- Includes off-design component performance submodels
- Inputs:
 - Pump inlet and outlet pressures
 - Heat source temperature & flow
 - Cooling water temperature and flow
 - PT speed
- Outputs:
 - TP speed
 - All other cycle points
 - Power output



EPS100 test program



- First commercial-scale sCO₂ heat engine operational in test environment
- Completed baseline performance and controls testing
- Component and system performance meets expectations, cycle model validated
- Endurance testing in process, will be followed by detailed system inspection